



L1358070001 – Montgomery
Eagle Zinc Company
ILD 930606941
SF/HRS

CERCLA

Expanded Site Inspection Addendum



Illinois Environmental
Protection Agency

**CERCLA
EXPANDED SITE INSPECTION ADDENDUM REPORT**

for:

Eagle Zinc Company

Hillsboro, Montgomery county, Illinois

ILD#: 980606941

**PREPARED BY:
ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
BUREAU OF LAND
DIVISION OF REMEDIATION MANAGEMENT
OFFICE OF SITE EVALUATION**

September 1, 2005

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1. INTRODUCTION	
1.1 INTRODUCTION.....	1
2. SITE BACKGROUND	
2.1 Site Description.....	2
2.2 Site History	4
2.3 Previous Investigations.....	4
2.4 Regulatory Status.....	6
3. EXPANDED SITE INSPECTION ACTIVITIES	
3.1 Sampling Activities.....	6
3.2 Analytical Results.	7
4. SITE SOURCES	
4.1 Waste Piles	8
5. MIGRATION PATHWAYS	
5.1 Groundwater Pathway.....	9
5.2 Surface Water Pathway.	10
5.3 Soil Exposure Pathway... ..	12
5.4 Air Pathway	13
6. ADDITIONAL RISK BASED OBJECTIVES	
6.1 Ontario Sediment and USEPA ECOTOX Threshold Benchmarks.	14
7 BIBLIOGRAPHY.....	15

THE FOLLOWING TABLES AND FIGURES ARE LOCATED AT THE BACK OF THE REPORT:

Figure

- 1 STATE OF ILLINOIS LOCATION MAP
- 2 REGIONAL AREA TOPOGRAPHIC MAP
- 3 AERIAL PHOTOGRAPH
- 4 SAMPLING LOCATION MAP

Table

- 1 SOIL SAMPLES DESCRIPTION TABLE
- 2 SEDIMENT SAMPLES DESCRIPTION TABLE
- 3 ONSITE WASTE PILES SAMPLES DESCRIPTION TABLE
- 4 SOIL KEY SAMPLES TABLE
- 5 SEDIMENT KEY SAMPLES TABLE
- 6 ONSITE WASTE PILES KEY SAMPLES TABLE
- 7 XRF SOIL SAMPLES TABLE
- 8 XRF SEDIMENT SAMPLES TABLE
- 9 XRF WASTE PILES SAMPLE SUMMARY

Appendix

- A SITE 4-MILE RADIUS MAP
- B 15-MILE SURFACE WATER ROUTE MAP
- C TARGET COMPOUND LIST AND DATA QUALIFIERS
- D IEPA SITE PHOTOGRAPHS
- E ANALYTICAL RESULTS (Volume 2)

SECTION 1.0 INTRODUCTION

1.1 Introduction

On September 24, 2004 the Illinois Environmental Protection Agency's (IEPA)'s Office of Site Evaluation was tasked by the United States Environmental Protection Agency (U. S. EPA) to conduct a Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) Expanded Site Inspection (ESI) Addendum investigation of the Eagle Zinc Company (ILD 980606941) site located on Industrial Park Drive in Hillsboro, Montgomery county, Illinois. The ESI was performed under the authority of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) commonly known as Superfund.

The objective of an Expanded Site Inspection (ESI) is to collect all data necessary to prepare a Hazard Ranking System (HRS) scoring package to propose the site to the National Priorities List (NPL). To fully evaluate the site and fulfill HRS documentation requirements, the ESI should:

- 1) Investigate and document critical hypotheses or assumptions not completely tested during previous investigations;
- 2) Collect samples to attribute hazardous substances to site operations;
- 3) Collect samples to establish representative background levels;
- 4) Collect any other missing HRS data for pathways of concern.

SECTION 2.0 SITE BACKGROUND

2.1 Site Description

The Eagle Zinc Company site is located on the west side of Industrial Park Drive in Hillsboro, Montgomery county, Illinois, at the northeast corner of Hillsboro, with a smaller section of vacant land lying east of Industrial Park Drive. It consists of approximately 132 acres and is legally described as having portions being located in the Southeast Quarter of Section One and the Northeast Quarter of Section twelve, T.8N, R.4W; and part of the Southwest Quarter of Section Six, T.8N, R3W. The surrounding area consists of Industrial Park Drive on the east side with vacant land beyond. Smith Road borders the north side with a recreational area lying to the north. The west side is irregular in shape and is bordered by Brailly Road on the north and vacant land further to the south. Houses lie along Brailly Road and along nearby streets further west. Private businesses, including a wood treating facility and lumber yard, lie south of the facility along Ash Street. The property contains approximately 132 acres of which approximately 26 were under roof. The buildings are located mainly on the east side of the site, with the area west of the buildings containing large piles of waste materials from the smelting and manufacturing activities. There are approximately 23 buildings remaining onsite. The activities that were conducted in the buildings included manufacturing/processing, office/laboratory, equipment, raw material and finished product storage, baghouses and maintenance.

There are two small ponds located at the northeastern portion of the property that discharges to a small brook that originates in the field located on the north side of the property. The brook flows east under Industrial Park drive and meanders to the northeast

were it enters Lake Hillsboro approximately 2500 feet from the site. A larger pond is located at the southwestern portion of the property. It consists of a slag dam constructed to contain runoff from large areas of slag and cinders located in the central and southwest area of the site. Runoff from the pond overflows from the dam on the west side and becomes part of a small brook. There is a drainage ditch on the south side of the property along an abandoned railroad right-of-way that drains west and joins with the dam overflow below the dam. The north bank of the ditch along Eagle Zinc property consists of a wall of slag and cinders in some places. The brook then flows west for approximately 1500 feet to an unnamed tributary of Middle Fork Shoal creek. It then flows north for approximately 3000 feet into Middle Fork shoal creek. The water then flows southwest approximately six miles and enters Shoal Creek.

Access to the property is via Industrial Park drive. There is a locked gate and the site has a low fence to prevent unauthorized vehicular access. There are no onsite employees nor guard to prevent people entering the property by climbing over the fence or where the fencing is absent or damaged. The nearest residents are located approximately 300 feet west of the property. The city of Hillsboro obtains its drinking water from surface water from Lakes Hillsboro and Glenn Shoals. The area shallow geology consists of approximately 50 to 100 feet of Pleistocene glacial till and outwash unconsolidated glacial deposits. Underlying the glacial deposits is bedrock consisting of the Pennsylvanian Bond Formation consisting mainly of limestone with some layers of shale and sandstone. Groundwater use in the area is limited since most people in the area are serviced by the Hillsboro water system.

2.2 SITE HISTORY

The property consists of a former zinc smelting and processing facility that began operations in 1912 as Lanyon Zinc Company and was sold to Eagle-Picher Industries in 1919. The facility was operated by Eagle Pitcher until 1980. The property was acquired by Sherman Williams in November 1980 who operated it until 1984. The facility was acquired in 1984 by Eagle Zinc Company, which is a division of T. L. Diamond Company of New York City. The facility ceased operations at the plant in 2003. Products produced during the years include: zinc, sulfuric acid, zinc oxide and leaded zinc oxide. The leaded zinc oxide was produced by combining zinc oxide with lead sulfate. The lead sulfate was obtained from outside sources. Waste materials generated included slag, rotary kiln residue, muffle dross, metallic zinc particles, and refractory brick.

2.3 Previous Investigations

The site was listed on CERCLIS in 1981. IEPA conducted a Preliminary Assessment in 1984. In 1980 and 1982 IEPA collected surface water samples for inorganic analysis. The water samples contained zinc, iron, lead and copper above state surface water standards and resulted in a Notice of Violation from IEPA. This resulted in Sherwin Williams removing approximately 18,000 tons of residue materials from 10 acres of the site. Analysis of residual materials by IEPA indicated that they were non-hazardous and not subject to RCRA (Resource Conservation and Recovery Act) permits.

In October 1993 IEPA conducted a CERCLA Expanded Site Inspection of the site and surrounding residential area. Samples collected onsite had elevated levels of arsenic, cadmium and lead. Some residential samples contained elevated levels of arsenic,

and the Illinois Department of Public Health indicated that levels of manganese were present that may pose a possible human health concern. Sediment samples collected had elevated levels of arsenic, cadmium, copper, lead and zinc.

Eagle Zinc entered into an Interim Consent Order with the Illinois Attorney General and IEPA in May 1998. As a result nine shallow monitoring wells were installed and sampled as well as the sampling of residual piles and underlying soils.

The facility was issued a National Pollutant Discharge Elimination Systems (NPDES) permit on June 20, 2000. As a requirement a two cell retention system was constructed at the northeast area of the property that would enable the settling of particles from runoff prior to discharging into the east offsite drainage pathway. This drainage pathway lead to Lake Hillsboro. The permit was terminated on May 23, 2003 after plant closing.

ENVIRON International Corporation (ENVIRON) of Deerfield, Illinois conducted a Remedial Investigation of the Eagle Zinc Company site on behalf of the Potential Responsible Parties (PRP). This was undertaken as part of the Remedial Investigation/Feasibility Study (RI/FS) for the site. According to ENVIRON the RI/FS is being undertaken pursuant to the Statement of Work contained in the December 31, 2001 Administrative Order on Consent between the PRP's and the U.S. Environmental Protection Agency (USEPA). A RI/FS work plan was completed in July 2002 and the following documents were generated: 1) Technical Memorandum, Phase 1-Source Characterization, March 2003; 2) Technical Memorandum, Phase 2-Migration Pathway Assessment, November 2003; 3) Daft Human Health Risk assessment, August 2004; and

Draft Ecological Risk Screening Evaluation, August 2004; 4) Draft RI report, November, 2004; 5) Final RI report, March 2005. (6) Addendum to RI Report, April 2005, (7) Draft Feasibility Study Report, April 2005.

2.4 Regulatory Status

Based upon available file information the Eagle Zinc Company site does not appear to be subject to Resource Conservation and Recovery Act (RCRA) corrective action authorities. Information currently available does not indicate that the site is under the authority of the Atomic Energy Act (AEA), Uranium Mine Tailings Action (UMTRCA), or the Federal Insecticide Fungicide or Rodenticide Act (FIFRA).

SECTION 3.0 EXPANDED SITE INSPECTION ACTIVITIES

3.1 Sampling Activities

Sampling activities were conducted on April 25, 26, 27 and 27, 2005. IEPA personnel collected a total of twelve onsite waste pile samples, twenty-one offsite soil/cinder samples including background samples, and eight sediment and one background sediment samples along the drainage pathway from the site to Lake Hillsboro. All samples were collected using stainless steel trowels and/or hand augers. All duplicate sample containers were filled in an alternating manner. Following sample collection, all samples were transferred to containers provided by the Illinois EPA's Division of Laboratories. The sample containers were packaged and sealed in accordance with the IEPA's Office of Site Evaluation procedures. Sample analysis were provided by USEPA's Contract Laboratory Program

(CLP), which utilizes a network of various laboratories throughout the United States. A complete analytical data package, including quality assurance review sheets, is located in Appendix E (Volume 2 of the Expanded Site Addendum Inspection report).

All samples were collected and shipped in accordance with the IEPA and USEPA procedures. All samples were analyzed for the Target Compound List (TCL) in Appendix C. During the April 2005 inspection waste pile and sediment semi-volatile soil organic samples were analyzed by A4 Scientific and inorganic waste pile, soil and sediment samples were analyzed by Chemtech Consulting Group. All laboratories were under contract with USEPA Region 5. All laboratory results were subsequently validated by USEPA Region 5.

3.2 Analytical Results

Sample locations are shown in Figure 4 and described in Tables 1, 2 and 3. Key sample analytical results from the sampling events are shown in Tables 4, 5 and 6. XRF soil, sediment and waste results are shown in Tables 7, 8 and 9. The analytical results for the soil samples were compared to Removal Action Levels (RAL's).

Key samples are samples in which contaminants were detected at concentrations at least three times background levels or had concentrations of potential health or environmental concerns. Samples meeting these criteria will be used to evaluate the site using the Hazard Ranking System (HRS). Analytes were found in offsite soil and sediment samples at levels that exceeded these health-based benchmarks. Analytes that exceeded health-based benchmarks included semivolatile compounds and inorganic substances.

SECTION 4.0 SITE SOURCES

This section includes descriptions of the various hazardous waste sources that have been identified at the Eagle Zinc Company site. The Hazard Ranking System defines a “source” as: “Any area where a hazardous substance has been stored, disposed or placed, plus those soils that have become contaminated from migration of hazardous substances”. This does not include surface water or sediments below surface water that become contaminated.

Information obtained during the Expanded Site Inspection identified waste piles and contaminated soil as the source of contamination at Eagle Zinc Company. As additional information becomes available, the possibility exists that additional sources of contamination may exist.

4.1 Waste Piles

Information obtained throughout the CERCLA investigation has identified onsite Waste piles as the primary source type at the Eagle Zinc Company site. The contamination was found at various locations throughout the site and the area of contamination is estimated to be approximately 35.72 acres. This is the area within sampling points X3101 – X303 – X304 – X305 – X306 – X307 – X308 – X310/X312 – X311 – X309- X313 – X301. See Figure 4 for sample locations. The analytical results from the samples collected onsite showed that a number of inorganic substances exceeded Removal Action Levels. These include cadmium, chromium, lead, zinc and others.

Section 5.0 MIGRATION PATHWAYS

The CERCLA program of Site Evaluation identifies three migration pathways and one exposure pathway, as identified in the Hazard Ranking System, by which hazardous substances may pose a threat to human health and/or the environment. Consequently, sites are evaluated on their known or potential impact to these pathways. The pathways are groundwater migration, surface water migration, soil exposure, and air migration.

5.1 Groundwater Pathway

The geology of the area consists of approximately 50 to 100 feet of Pleistocene glacial till and outwash unconsolidated glacial deposits. Underlying the glacial deposits is bedrock consisting of the Pennsylvanian Bond Formation consisting mainly of limestone with some layers of shale and sandstone.

Groundwater use for drinking in the area is limited. The city of Hillsboro uses surface water for potable water. Some private wells are located within a quarter mile of the site but local residents are prohibited from connecting private wells into their household systems so that cross contamination can be avoided. The villages of Taylor Springs, located adjacent to the south side of Hillsboro, and Schram City, located adjacent to the east side of Hillsboro, obtain their drinking water from Hillsboro. Hillsboro also supplies water to portions of outlying areas through the Montgomery County Rural Water District. Areas not served by the Hillsboro water distribution system used groundwater for drinking. Groundwater flow in the vicinity of the site is not known.

The number of people who use groundwater in a four-mile radius of the site was estimated using information obtained from the Illinois EPA Public Water Supplies records,

USGS topographic maps and the average persons per household in Montgomery. The estimated population is:

Estimated Groundwater Target Population

Onsite	0
0 to 1/4 mile	0
>1/4 to 1/2 mile	0
>1/2 to 1 mile	17
>1 to 2 miles	73
>2 to 3 miles	129
>3 to 4 miles	132

Since there is no nearby residential groundwater use no groundwater samples were collected during the April 2005 ESI Addendum inspection. Onsite monitoring well samples collected by ENVIRON in March 2003 indicate that some samples contained certain inorganic substances that exceeded TACO Class 1 groundwater standards. These included arsenic, cadmium, lead and zinc.

5.2 Surface Water Pathway

This pathway begins where surface water run-off from the site enters the first perennial water body. This is the Probable Point of Entry (PPE) into surface water. This pathway then travels fifteen miles downstream from the PPE completing the 15-mile Target Distance Limit (TDL).

Eagle Zinc Company would drain surface runoff into two different routes. The

western surface water pathway drains the southwest area of the property into an onsite pond. The overflow from the pond joins with a ditch which runs along the south side of the site. The ditch on the south side has waste piles from the site along its north bank. The pathway then flows west into an intermittent stream and then north approximately one mile into Middle Fork Shoal Creek, a perennial waterway. This is one PPE into surface water.

The second surface water pathway is located at the northeast area of the site and drains much of the northern portion of the property. The pathway originates in a field at the north portion of the site and flows northeast for approximately one-half mile and enters Lake Hillsboro. This is the Probable Point of Entry (PPE) into surface water that will be evaluated for this site. Lake Hillsboro is used locally as a drinking water source and for recreational activities such as fishing and boating. The surface water intake for the lake is located approximately one mile downstream from the PPE. Water from Lake Hillsboro and Lake Glenn Shoals are blended and used as a drinking water source for Hillsboro, Schram City, Taylor Springs, Coffeen, Graham Correctional Center and the Montgomery County Rural Water District. Lake Glenn Shoals is not located along the sites' surface water pathway. The proportion supplied by Lake Hillsboro varies according to the season but the Plant Water Operator and Supervisor estimates that it would be approximately twenty percent of the yearly average. The two lakes supply water to a total of 8,959 people, with Lake Hillsboro supplying an annual average of 1,792 people.

The 15-mile Target Distance Limit extends approximately one mile in Lake Hillsboro, ten miles in Middle Fork Shoal creek and four miles in Shoal Creek. According to the Flood Hazard Boundary Map the site is not located in any floodplain. The nearest

wetlands are the three ponds located onsite and are classified as a Palustrine unconsolidated bottom intermittently exposed diked/impounded wetland. There are approximately 18 miles of wetland frontage along the fifteen-mile surface water pathway in Lake Hillsboro and Middle Shoal creek. According to the Illinois Department of Natural Resources there are no threatened or endangered species within a mile of the site or in the 15 mile downstream mileage.

Sediment samples collected onsite and along the drainage pathway leading to Lake Hillsboro during the inspection contained a number of semi-volatile and inorganic substances that are attributable to the site. These include samples X202, X203/X204, X205, X206, 207, X208, X209 and X210. These substances exceeded sediment background sample X201 collected from Lake Hillsboro north of the site. They also exceed Ontario Sediment thresholds. Contaminants found include benzo(b)fluoranthene, benzo(g,h,i)perylene, cadmium, lead, nickel and zinc. The Probable Point of Entry (PPE) into surface water is sample X210 collected at the point where the offsite drainage enters Lake Hillsboro.

5.3 Soil Exposure Pathway

This exposure pathway focuses on contaminated soil in the upper two feet of the ground surface and within 200 feet of an occupied residence.

Eagle Zinc Company is situated at the northeast side of Hillsboro, IL. Access is partially limited by fencing and a locked gate. Private residences are located approximately 300 feet near the west side of the site across Brailly Road. The nearest worker is approximately 250 feet south in the businesses located on the north side of Route 16. The nearest school is located approximately nine-tenths of a mile southwest of the site in

Hillsboro. A review of USGS topographic maps, city maps and U.S. Census data indicate that there are approximately 3,459 people that live within a one-mile radius of the site. The estimated population within one mile of the site is:

Onsite	0
0 to ¼ mile	283
¼ to ½ mile	697
½ to 1 mile	2,479

Soil samples collected during the 2005 Expanded Site Inspection Addendum document areas of observed contamination by contaminants that are attributable to the site. These included a number of inorganic substances, including cadmium, lead and zinc. The property is partially fenced to prevent unauthorized access although trespassers can enter from breaks in the fence or through the west side. The property has a locked gate but there is no guard of watchman overseeing the property.

5.4 Air Pathway

The Eagle Zinc Company property is sparsely vegetated with exposed piles of wastes. During the April 2005 ESI Addendum inspection dust was observed blowing from some of the piles. The site is fenced with a locked gate and access is limited. Access by car or truck is not possible although it may be possible to access the site by ATV. There are no workers onsite. Houses are located approximately 300 feet west and the nearest school is located approximately nine-tenths of a mile southwest of the site in Hillsboro. Graham Correctional Center is located approximately two miles south and has about 1,400 inmates

and workers. There are approximately 7,346 people who live within a 4-mile radius of the site. The estimated population potential for release is:

Estimated Air Target Population	
Onsite	0
0 to ¼ mile	283
¼ to ½ mile	697
½ to 1 mile	2,479
1 to 2 miles	2,167
2 to 3 miles	1,588
3 to 4 miles	132

Wetland inventory maps indicate that there is approximately 17 acres of wetlands located within a half-mile of the site.

SECTION 6 ADDITIONAL RISK BASED OBJECTIVES

This section discusses additional screening objectives used to evaluate the Eagle Zinc Company site. These objectives have not been used to assess the site for Hazard Ranking System (HRS) purposes.

6.1 Ontario Sediment and USEPA ECOTOX Threshold Benchmarks

Sediment samples collected in the drainage pathway leading to Lake Hillsboro were compared to Ontario Sediment (low level) and USEPA ECOTOX Threshold benchmarks. Several sediment samples exceeded these benchmarks for inorganic substances. They included arsenic, cadmium, lead and zinc.

SECTION 7.0 REFERENCES

IEPA BOL Files. CERCLA Expanded Site Inspection Report for Eagle Zinc Co., 1994.

ENVIRON International Corporation. Remedial Investigation Report for Eagle Zinc Company Site, Hillsboro, IL. November 2004.

Illinois Department of Natural Resources. Endangered Species Information Request letter of September 1, 2005 for Eagle Zinc Co.

United States Department of the Interior, National Wetlands Inventory Maps for Hillsboro, Butler and Sorento North, IL. Quadrangles, 7.5 minute series.

USGS, 1974, Butler, IL. Quadrangle, 7.5 minute series.

USGS, 1974, Sorento North, IL. Quadrangle, 7.5 minute series.

USGS, 1974, Hillsboro, IL. Quadrangle, 7.5 minute series.

USGS, 1974, Coffen, IL. Quadrangle, 7.5 minute series.

U S. Census Bureau, American FactFinder website. Table GCT-H6. Occupied Housing Characteristics: 2000.

Illinois Environmental Protection Agency, Division of Public Water Supplies. Public Water Supply Data Sheet for Facility No. 1350300 – Hillsboro – Montgomery County. Inspection date: March 31, 2005.

Phone conversation with Roger Fath, Operator and Water Treatment Plant Supervisor for the city of Hillsboro, July 21, 2005 concerning relative contributions of Lakes Hillsboro and Glenn Shoals to local water supply.

IEPA Site Reconnaissance visit of March 16, 2005 to Eagle Zinc Co.

Flood Hazard Boundary Map, Montgomery County, IL. Panel 6 of 9. Federal Emergency Management Agency, January 9, 1981.



Figure 1

Eagle Zinc Company

STATE OF ILLINOIS LOCATION MAP




Figure 2
Regional Area Topographic Map

0 850 1,700 3,400 5,100 6,800 Feet



Source: United States Geological Survey Topographical Map
in Digital Raster Graphic Format, 1:100,000 Scale
Quadrangle Index # 39089b44

Figure 3
Eagle Zinc Company
Aerial Photograph



0 0.05 0.1 0.2 0.3 0.4
Miles

Source: Illinois Department of Natural Resources
Geospatial Data Clearinghouse:
Digital Orthographic Quadrangles, 1999, accessed 2005

Legend

Site Boundary





Figure 4
Eagle Zinc Company
Sample Location Map

- Legend**
- Soil
 - Sediment
 - Waste
 - Site Boundary



0 0.05 0.1 0.2 0.3 0.4
Miles

Source: Illinois Department of Natural Resources
Geospatial Data Clearinghouse:
Digital Orthographic Quadrangles, 1999, accessed 2005

TABLE 1 OFFSITE SOIL/WASTE SAMPLE DESCRIPTIONS		
X101		Not collected
X102		Not collected.
X103		Not collected.
X104 4/27/2005 11:40	Inorganics - 0 to 1"	Brown-black clay.
X105/ X115 4/27/2005 14:10	Inorganics - 1/2" to 3"	Cinders, slag material, black fines. Duplicate samples.
X106 4/27/2005 12:00	Inorganics - 0 to 2"	Brown-black clay loam.
X107 4/27/2005 10:50	Inorganics - 0 to 1"	Slag material over clay.
X108 4/27/2005 12:30	Inorganics - 0 to 2"	Light brown clay loam.
X109 4/27/2005 17:20	Inorganics - 0 to 2"	Brown silty clay.
X110 4/27/2005 10:10	Inorganics - 0 to 2"	Gravel, black fill material, cinders, metal pieces.
X111 4/27/2005 9:30	Inorganics - 0 to 1"	Black silty loam.
X112 4/27/2005 9:50	Inorganics 0 - 2"	Reddish brown cinders and slag.
X113 4/26/2005 12:50	Inorganics 1" - 3"	A mixture of black cinders and Soil.

TABLE 1
OFFSITE SOIL/WASTE SAMPLE DESCRIPTIONS
(Continued)

SAMPLE	DEPTH	APPEARANCE
X114 4/27/2005 12:50	Inorganics - 0 to 3"	Light brown clay loam.
X115/ X105 4/27/2005 14:10	Inorganics - 1/2" to 3"	Cinders, slag material, black fines. Duplicate samples.
X116 4/27/2005 14:50	Inorganics - 0 to 3"	Brown gray silty clay.
X117		Not collected.
X118 4/27/2005 15:50	Inorganics - 1" to 3"	Dark brown silty clay.
X119 4/28/2005 9:40	Inorganics - 0 to 2"	Black silty loam.
X120/ X121 4/28/2005 8:40	Inorganics - 0 to 1"	Light brown silty clay. Duplicate samples.
X122 4/27/2005 19:20	Inorganics - 2" to 3"	Brown silty loam, some roots.
X123 4/27/2005 18:50	Inorganics - 0 to 3"	Black silty loam with cinders.
X124 4/27/2005 18:00	Inorganics - 3" to 6"	Fine black slag material.
X125 4/27/2005 17:40	Inorganics - 0 - 3"	Black loam with medium size gravel.
X126 4/28/2005 9:00	Inorganics - 0 - 1"	Dark brown silty clay.

TABLE 2
SEDIMENT DESCRIPTIONS

SAMPLE	DEPTH	APPEARANCE
X201 4/27/2005 15:20	Inorganics - 2" to 4" Semi - 2" to 4"	0 to 6" - Brownish gray silty clay.
X202 4/27/2005 8:50	Inorganics - 0 to 2" Semi - 4"	0 to 3" - Gray silty clay. 3" to 6" - Light tan silty clay.
X203/ X204 4/26/2005 18:40	Inorganics - 0 to 2" Semi - 1" to 3"	0 to 3" - Brown silty clay.
X205 4/26/2005 17:40	Inorganics - 0 to 1/2" Semi - 2" to 4"	0 to 3" - Brown silty clay. 3" to 6" - Brownish gray silty clay, roots. 6" - Brownish gray silty clay, roots.
X206 4/26/2005 17:00	Inorganics - 3" to 5" Semi - 3" to 5"	0 to 3" - Brown silty clay. 3" to 6" - Brown clay, some silt, few medium rocks. 6" to 12" - Brown gray clay, little silt.
X207 4/26/2005 15:00	Inorganics - 3" to 4" Semi - 4"	0 to 3" - Brown silt, a little sand and clay. 3" to 6" - Brown silt, a little sand and clay. 6" - Brown silt, a little sand and clay.
X208 4/26/2005 14:30	Inorganics - 0 to 2" Semi - 4"	0 to 3" - Brown silt. 3" to 6" - Sand, some brown clay. 6" - Sand, some brown clay.
X209 4/26/2005 13:40	Inorganics - 0 to 3" Semi - 4"	0 to 3" - Brown silty clay; some organic matter. 3" to 6" - Brownish gray silty clay; more organic matter and some sand. 6" - Silty clay with a little sand.
X210 4/26/2005 10:30	Inorganics - 3" to 5" Semi - 3" to 5'	0 to 3" - Brownish gray silty clay. 3" to 6" - Brownish gray silty clay with some organic matter.

TABLE 3
Onsite Waste Sample Descriptions

SAMPLE	DEPTH	APPEARANCE
X301 4/25/2005 15:20	Inorganics - 0 to 2" SVOC's - 4"	Fine black cinder material collected from a pile onsite.
X302 4/25/2005 15:40	0 to 2" SVOC's - 4"	Fine black cinder material collected from a pile onsite.
X303 4/25/2005 16:00	Inorganics - 0 to 2" SVOC's - 4"	Brownish - grey fine slag material collected from a pile onsite.
X304 4/25/2005 16:10	Inorganics - 0 to 2" SVOC's - 4"	Orange - brown slag fines collected from a pile onsite.
X305 4/25/2005 16:30	Inorganics - 0 to 2" SVOC's - 4"	Black - brown slag fines collected from a pile onsite.
X306 4/25/2005 17:20	Inorganics - 0 to 1/2" SVOC's - 4"	Grey slag and cinder material collected from a pile onsite.
X307 4/25/2005 17:40	Inorganics - 0 to 1/2" SVOC's - 4"	Brown - grey slag fines; some brick shards collected from a pile onsite.
X308 4/25/2005 18:15	Inorganics - 0 to 1/2" SVOC's - 4"	Light -grey slag fines collected from a pile onsite.
X309 4/26/2005 8:10	Inorganics - 0 to 1/2" SVOC's - 4"	Medium grey slag fines with metal shavings collected from a pile onsite.
X310/ X312 4/26/2005 8:45	Inorganics - 0 to 1/2" SVOC's - 4"	Fine medium grey slag material collected from a pile onsite. Duplicate samples.
X311 4/26/2005 8:30	Inorganics - 0 to 1/2" SVOC's - 2 to 3"	Medium grey slag fines collected from a pile onsite.
X313 4/26/2005 9:30	Inorganics - 0 to 1/2" SVOC's - 3" to 4"	Light grey slag fines, some coarse white slag.

Eagle Zinc Company
ILD 908606941

TABLE 4
Soil Key Samples

Sampling Location : Date Sampled :	X118 4/27/05 (Background)	X104 4/27/05	X105 4/27/05	X106 4/27/05	X107 4/27/05	X108 4/27/05	X109 4/27/05	X110 4/27/05	X111 4/27/05	X112 4/27/05	X113 4/27/05	X114 4/27/05	RAL's
INORGANICS													
ANTIMONY	7.5	UJ	--	--	--	--	--	--	--	--	22.2	--	--
CADMIUM	0.97		9.7	29.2	--	5.4	--	--	--	--	6	6.5	25
COPPER	10.8		86.5	241	--	178	--	146	--	124	1710	139	5,000
LEAD	34.4		--	408	--	155	--	267	164	417	401	287	1,000
MANGANESE	1380		1380	--	798	958	--	728	--	--	809	--	--
NICKEL	10.5		--	--	--	8.6	--	--	--	--	439	--	1,600
THALLIUM	3.1	U	--	--	--	3.1	U	--	--	--	--	--	55
ZINC	595		8870	19200	--	7610	463	--	9440	--	4080	70600	18200
CYANIDE	0.21	UJ	--	--	--	--	--	--	--	--	0.11	J	350
	mg/Kg		mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg

Eagle Zinc Company
ILD 908606941

TABLE 4
Soil Key Samples
(Continued)

(Continued)																	
Sampling Location : Date Sampled :	X118 4/27/05 (Background)	X115 4/27/05	X116 4/27/05	X119 4/28/05	X120 4/28/05	X121 4/28/05	X122 4/27/05	X123 4/27/05	X124 4/27/05	X125 4/27/05	X126 4/28/05	RAL's					
INORGANICS																	
ANTIMONY	7.5	UJ	--	1.4	J	--	--	1.2	J	11.2	J	8.6	J	1.9	J	--	--
CADMIUM	0.97		34.6	0.53	J	9.1	1.3	0.45	J	--	19.2	12.8	6.7	--	--	25	25
COPPER	10.8		219	13.3		57.8	17.3	15		--	163	375	62.8	--	--	5,000	5,000
LEAD	34.4		469	27.1	J	273	J	48.8	J	37.9	J	213	J	534	2450	218	1,000
MANGANESE	1380		--	1500	--	J	667	J	781	J	1260	J	1050	--	781	--	--
NICKEL	10.5		--	15.1	--	--	15	12.6	--	31	--	--	--	--	--	1,600	1,600
THALLIUM	3.1	U	--	--	--	--	--	--	--	2.6	J	--	--	--	--	55	55
ZINC	595		22400	397	6030	461	264	--	2220	13200	2830	--	--	--	--	160,000	160,000
CYANIDE	0.21	UJ	--	--	0.25	J	0.19	J	0.21	J	1.4	J	--	--	--	350	350
	mg/Kg		mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg

Eagle Zinc Company
ILD 908606941

TABLE 5
Key Sediment Samples

Sampling Location : Date Sampled : (Background)	X201 4/27/05	X202 4/27/05	X203 4/26/05	X204 4/26/05	X205 4/26/05	X206 4/26/05	X207 4/26/05	X208 4/26/05	X209 4/26/05	X210 4/26/05	Ontario Sediment	USEPA Ecotox
Benzo(b)fluoranthene	--	--	--	--	--	--	59 J	--	--	--	--	--
Benzo(g,h,i)perylene	--	--	--	--	--	--	48 J	--	83 J	--	--	--
Fluoranthene	--	--	--	62 J	--	--	--	--	--	--	--	2900
	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg		
INORGANICS:												
ANTIMONY	16.1 UJ	21.9 J	5.1 J	7.3 J	7.7 J	--	3.1 J	--	6 J	--	--	--
ARSENIC	7.1 J	6.3 J	7.2 J	8.3 J	13.2	--	11.9	--	26.4	--	6	--
CADMIUM	1.4	13.2	15.9	14.2	14.3	5.8	3.4	12.6	7	16.1	0.6	--
COBALT	5.8 J	--	--	20.1	23.2	--	--	--	49.9	--	50	--
COPPER	95.5	297	203	238	144	34.7	51.8	41.6	65	81.5	16	--
IRON	11300	--	--	--	23200	--	21200	--	34300	--	20,000	--
LEAD	45.6	630	383	439	769	121	188	109	333	142	31	--
MANGANESE	1040	--	--	--	3100	575	979	--	3640	--	460	--
NICKEL	11.7	144	67.6	76.4	48	--	--	--	24.7	--	16	--
SILVER	2.7 U	--	1.8	1.7	0.51 J	--	--	--	--	--	0.5	--
ZINC	1080	26600	29100	31300	13400	5300	7870	3910	7350	8120	120	--
CYANIDE	0.33 UJ	--	--	--	0.38 J	0.1 J	0.09 J	0.12 J	0.12 J	0.33 J	0.1	--
pH	6.3	6.8	6.6	6.5	6.6	6.5	6.7	6.9	5.9	5.9	--	--
	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg

Eagle Zinc Company
ILD 908606941

TABLE 6
Waste Pile Key Samples

Sampling Location :	X301	X302	X303	X304	X305	X306	X307	X308	X309	X310	X311	X312	X313	RAL's	
Date Sampled :	4/25/05	4/25/05	4/25/05	4/25/05	4/25/05	4/25/05	4/25/05	4/25/05	4/26/05	4/26/05	4/26/05	4/26/05	4/26/05		
SEMIVOLATILES:															
Phenol	48	J	--	--	--	--	--	--	--	--	--	--	--	470,000,000	
Phenanthrene	61	J	--	--	--	--	90	J	--	--	--	--	--	1,000,000	
Fluoranthene	120	J	71	J	--	--	250	J	--	--	--	--	74	J	1,000,000
Pyrene	100	J	54	J	--	--	170	J	--	--	--	--	49	J	1,000,000
Benzo(a)anthracene	51	J	--	--	--	--	88	J	--	--	--	--	--	--	1,000,000
Chrysene	110	J	40	J	--	--	150	J	--	--	--	--	66	J	1,000,000
Benzo(b)fluoranthene	110	J	41	J	--	--	130	J	--	--	--	--	68	J	--
Benzo(k)fluoranthene	--	--	--	--	--	--	57	J	--	--	--	--	--	--	1,000,000
Benzo(a)pyrene	43	J	--	--	--	--	65	J	--	--	--	--	--	--	1,000,000
Benzo(g,h,i)perylene	55	J	--	--	--	--	50	J	--	--	--	--	--	--	1,000,000
	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/Kg	ug/kg	
INORGANICS:															
ALUMINUM	6860	4000	5530	4490	3910	4890	4150	41400	39800	75500	47200	58600	4840	310	
ANTIMONY	13.3	13	28.6	355	13.1	6.7	320	429	665	628	621	608	109	--	
ARSENIC	11.1	7	158	124	37.1	26.7	141	48.1	34.2	61.1	52.6	53.4	175	200	
CADMIUM	88.5	--	67.4	--	30.4	17.6	152	--	60.5	29	42	34.9	97.8	25	
CHROMIUM	--	--	--	--	--	--	--	902	--	1460	1620	1480	--	400	
COBALT	18.9	417	30.2	103	16.5	12.5	10.7	60.9	34.5	114	79.9	72.8	21	--	
COPPER	--	--	--	--	--	--	--	21900	33100	20300	19800	23900	--	5000	
LEAD	3190	--	5680	36500	7860	7390	7230	20300	13000	16800	18400	16400	29100	1,000	
MANGANESE	517	374	231	5200	151	188	492	707	1280	1080	938	1120	471	--	
NICKEL	--	--	--	--	--	--	--	9100	5350	17200	13000	9110	--	1,600	
ZINC	--	391000	--	--	--	--	194000	381000	258000	383000	407000	354000	387000	160,000	
pH	6.6	6.5	6.8	6.4	6.4	6.8	5.9	5.8	6.1	6	6.7	6.5	6.2	--	
	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg

NOTE: No background sample was collected to compare these samples against.

Eagle Zinc Company
ILD 980606941

TABLE 7
XRF Sample Summary
(Soil)

Sample No.	Depth	XRF No.	Date/Time	Pb	As	Hg	Zn	Cu	Ni	Mn	Cr	Ba
X104	0 to 1"	186	4/27/2005 12:43	85	--	--	13888	--	--	--	--	--
X106	0 to 2"	191	4/27/2005 13:12	--	--	--	490.8	--	--	--	--	--
X107	0 to 1"	183	4/27/2005 11:44	143.2	--	--	11897.6	491.6	--	--	--	--
X108	0 to 2"	194	4/27/2005 13:32	--	--	--	312.2	--	--	--	--	--
X109	Surface	211	4/27/2005 18:14	35	--	--	365.6	--	--	--	--	--
	3"	212	4/27/2005 18:15	--	--	--	940	--	--	--	--	--
	6"	213	4/27/2005 18:18	37.5	--	--	629.6	--	--	--	--	--
X110	0 to 2"	182	4/27/2005 11:22	205.8	--	--	8819.2	--	--	--	--	--
X111	0 to 1"	175	4/27/2005 10:29	107.6	--	--	1480	--	402.8	--	--	--
X112	Surface	177	4/27/2005 10:48	190.2	--	--	4819.2	--	--	--	--	--
	6"	178	4/27/2005 10:50	106.4	--	--	5568	--	1309.6	--	--	--
X113	Surface	125	4/26/2005 13:49	460.8	--	--	42880	760.4	--	--	--	--
	3"	126	4/26/2005 13:51	474.4	--	--	55961.6	850.4	1880	1840	--	--
	6"	127	4/26/2005 13:56	314.2	--	--	113971.2	3628.8	2059.2	--	--	--
X114	Surface	195	4/27/2005 14:00	157.5	--	--	14489.6	--	--	--	--	--
	3"	196	4/27/2005 14:03	163.3	--	--	7769.6	--	--	--	--	--
	6"	197	4/27/2005 14:06	155.6	--	--	4668.8	--	2169.6	1120	606.8	--
X115/X105	Surface	200	4/27/2005 15:10	473.6	--	--	21593.6	--	--	--	--	--
	3"	201	4/27/2005 15:16	301.8	--	--	24000	--	--	--	--	--
X116	Surface	202	4/27/2005 15:44	--	--	--	279.2	--	--	--	--	--
	3"	203	4/27/2005 15:45	--	--	--	350.2	--	--	--	--	--
X118	Surface	206	4/27/2005 16:55	--	46.4	--	450.4	--	--	--	--	--
	3"	207	4/27/2005 16:57	--	--	--	334	--	--	555.6	--	--
X119	Surface	240	4/28/2005 10:31	35.6	--	--	6137.6	--	--	--	--	--
	3"	241	4/28/2005 10:34	71.9	--	--	3379.2	--	--	--	--	--
	6"	242	4/28/2005 10:37	50.8	--	--	1320	--	--	--	--	--
X120/X121	Surface	236	4/28/2005 9:39	--	--	--	118	--	--	--	--	--
	3"	237	4/28/2005 9:42	40.7	--	--	426.8	--	--	990.4	718	--
X122	3"	229	4/27/2005 20:37	230.2	--	--	924	--	--	--	--	--
X123	Surface	220	4/27/2005 19:55	238.2	--	--	1009.6	--	--	493.6	--	--
	3"	221	4/27/2005 19:57	556	--	--	2428.8	312.2	--	1040	--	--
	6"	222	4/27/2005 20:00	328	--	--	930.4	--	--	--	--	--
X124	Surface	217	4/27/2005 19:02	736.8	--	--	6918.4	--	--	--	--	--
	3"	218	4/27/2005 19:04	1100	--	--	9747.2	499.6	--	--	--	--
	6"	219	4/27/2005 19:05	2360	--	--	14899.2	700.4	--	--	--	--
X125	Surface	215	4/27/2005 18:41	130.4	--	--	2089.6	--	--	--	--	--
	3"	216	4/27/2005 18:43	131.1	--	--	1760	--	--	--	--	--
X126	Surface	238	4/28/2005 10:08	42.4	--	--	414	--	--	302.4	--	--
	3"	239	4/28/2005 10:11	38.4	21.6	--	482.8	--	--	--	--	--
				ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm

Eagle Zinc Company
ILD 980606941

TABLE 8
XRF Sample Summary
(Sediment)

Sample No.	Depth	XRF No.	Date/Time	Pb	As	Hg	Zn	Cu	Ni	Mn	Cr	Ba
X201	Surface	204	4/27/2005 16:37	--	--	--	356.2	88.9	--	--	--	--
	6"	205	4/27/2005 16:39	--	--	--	239.6	--	--	--	--	--
X202	Surface	171	4/27/2005 9:43	421.2	--	--	33894.4	--	--	--	--	--
	3"	172	4/27/2005 9:44	397.8	--	--	28492.8	522.8	--	--	--	--
	6"	173	4/27/2005 9:46	292.8	--	--	16294.4	--	1109.6	--	--	--
X203/X204	0 to 1/2"	163	4/26/2005 19:43	166.1	--	--	17996.8	289.4	--	470	--	--
X205	0 to 1/2"	160	4/26/2005 18:58	491.6	--	--	9939.2	--	--	1200	--	--
X206	Surface	147	4/26/2005 17:40	71.2	--	--	5699.2	--	--	550.4	--	--
	3"	148	4/26/2005 17:50	123.2	--	--	9728	--	--	--	--	--
	6"	149	4/26/2005 17:51	112.2	--	--	9689.6	--	--	--	--	--
	12"	150	4/26/2005 17:54	90.1	--	--	9824	--	--	--	--	--
X207	Surface	142	4/26/2005 15:49	131.6	--	--	7795.2	--	--	--	--	--
	3"	143	4/26/2005 15:51	140.2	--	--	6726.4	217.6	--	--	--	--
	6"	144	4/26/2005 15:52	138.7	--	--	6128	--	--	--	--	--
X208	Surface	134	4/26/2005 15:12	101	--	--	2160	--	--	--	--	--
	3"	135	4/26/2005 15:14	70.6	--	--	1659.2	--	--	2859.2	--	--
	6"	136	4/26/2005 15:15	62.4	--	--	2179.2	--	--	774	--	--
X209	Surface	128	4/26/2005 14:24	80.5	--	--	3849.6	--	1100	--	--	--
	3"	129	4/26/2005 14:26	97.3	--	--	4339.2	--	251.2	--	--	--
	6"	130	4/26/2005 14:29	61.2	--	--	1840	--	289.4	--	--	--
X210	Surface	108	4/26/2005 11:33	88.9	--	--	5187.2	--	192.6	--	--	--
	Surface (Am)	109	4/26/2005 11:35	--	--	--	--	--	--	--	--	192.4
	3" (Am)	110	4/26/2005 11:37	--	--	--	--	--	--	--	--	202.1
	3"	111	4/26/2005 11:38	96.3	--	--	5987.2	--	--	--	--	--
	6"	112	4/26/2005 11:40	102.3	--	--	4057.6	161.1	203.9	--	--	--
	6" (Am)	113	4/26/2005 11:41	--	--	--	--	--	--	--	--	293.8
	12" (Am)	114	4/26/2005 11:42	--	--	--	--	--	--	--	--	--
	12"	115	4/26/2005 11:45	35.8 ppm	-- ppm	-- ppm	1389.6 ppm	-- ppm	-- ppm	-- ppm	-- ppm	-- ppm

Eagle Zinc Company
ILD 980606941


TABLE 9
XRF Sample Summary
(Waste Piles)

Sample No.	Depth	XRF No.	Date/Time	Pb	As	Hg	Zn	Cu	Ni	Mn	Cr	Ba
X301	0 to 2"	84	4/25/2005 16:29	1739.2	--	--	84377.6	1349.6	918.4	1969.6	1200	--
X302	0 to 2"	85	4/25/2005 16:43	--	--	--	930611.2	14694.4	4387.2	--	--	--
X303	0 to 2"	87	4/25/2005 17:02	5308.8	--	--	155955.2	7737.6	--	--	--	--
X304	0 to 2"	88	4/25/2005 17:20	43392	--	--	42880	5440	--	19097.6	--	--
X305	0 to 2"	89	4/25/2005 17:36	7494.4	--	--	59955.2	2489.6	--	--	--	--
X306	0 to 1/2"	90	4/25/2005 18:24	9388.8	--	143.5	91750.4	3459.2	--	--	--	--
X307	0 to 1/2"	94	4/25/2005 18:58	6067.2	617.2	--	226918.4	5987.2	--	--	--	--
	4"	95	4/25/2005 18:59	10297.6	894.4	--	401817.6	8275.2	--	--	--	--
X308	0 to 1/2"	96	4/25/2005 19:18	27289.6	--	--	529.638026	80281.6	32384	--	--	--
X309	0 to 1/2"	104	4/26/2005 9:16	10496	--	--	553779.2	41292.8	6377.6	--	--	--
X311	0 to 1/2"	105	4/26/2005 9:35	19392	--	--	196.755596	55961.6	33587.2	--	--	--
X310/312	0 to 1/2"	106	4/26/2005 9:56	13798.4	--	--	853606.4	43596.8	27596.8	5068.8	--	--
X313	0 to 1/2"	107	4/26/2005 10:37	24588.8	--	--	841318.4	18188.8	--	--	--	--
				ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm

APPENDIX A

SITE 4-MILE RADIUS MAP

EAGLE ZINC COMPANY




4-Mile Radius Map Eagle Zinc Company

Legend

- Surface Water Intake
- Private Well
- Site Location

Source: United States Geological Survey Topographical
Map in Digital Raster Graphic Format,
1:100,000 Scale Quadrangle, Index # f39089a1

0 0.5 1 2 3 4 Miles




APPENDIX B

15 – MILE SURFACE WATER MAP

EAGLE ZINC COMPANY

33




Source: United States Geological Survey Topographical Map in Digital Raster Graphic Format, 1:100,000 Scale Quadrangle, Index # f39089a1

15-Mile Surface Water Pathway Map

Eagle Zinc Company

Legend

- Surface Water Intake
- Surface Water Pathway
- Site Location



0 0.5 1 2 3 4 Miles

APPENDIX C

TARGET COMPOUND LIST AND DATA QUALIFIERS

EAGLE ZINC COMPANY

TARGET COMPOUND LIST

Volatile Target Compounds

Chloromethane	1,2-Dichloropropane
Bromomethane	cis-1,3-Dichloropropene
Vinyl Chloride	Trichloroethene
Chloroethane	Dibromochloromethane
Methylene Chloride	1,1,2-Trichloroethane
Acetone	Benzene
Carbon Disulfide	trans-1,3-Dichloropropene
1,1-Dichloroethene	Bromoform
1,1-Dichloroethane	4-Methyl-2-pentanone
1,2-Dichloroethene (total)	2-Hexanone
Chloroform	Tetrachloroethene
1,2-Dichloroethane	1,1,2,2-Tetrachloroethane
2-Butanone	Toluene
1,1,1-Trichloroethane	Chlorobenzene
Carbon Tetrachloride	Ethylbenzene
Vinyl Acetate	Styrene
Bromodichloromethane	Xylenes (total)

Base/Neutral Target Compounds

Hexachloroethane	2,4-Dinitrotoluene
bis(2-Chloroethyl) Ether	Diethylphthalate
Benzyl Alcohol	N-Nitrosodiphenylamine
bis (2-Chloroisopropyl) Ether	Hexachlorobenzene
N-Nitroso-Di-n-Propylamine	Phenanthrene
Nitrobenzene	4-Bromophenyl-phenylether
Hexachlorobutadiene	Anthracene

2-Methylnaphthalene	Di-n-Butylphthalate
1,2,4-Trichlorobenzene	Fluoranthene
Isophorone	Pyrene
Naphthalene	Butylbenzylphthalate
4-Chloroaniline	bis(2-Ethylhexyl)Phthalate
bis(2-chloroethoxy)Methane	Chrysene
Hexachlorocyclopentadiene	Benzo(a)Anthracene
2-Chloronaphthalene	3-3'-Dichlorobenzidene
2-Nitroaniline	Di-n-Octyl Phthalate
Acenaphthylene	Benzo(b)Fluoranthene
3-Nitroaniline	Benzo(k)Fluoranthene
Acenaphthene	Benzo(a)Pyrene
Dibenzofuran	Ideno(1,2,3-cd)Pyrene
Dimethyl Phthalate	Dibenz(a,h)Anthracene
2,6-Dinitrotoluene	Benzo(g,h,i)Perylene
Fluorene	1,2-Dichlorobenzene
4-Nitroaniline	1,3-Dichlorobenzene
4-Chlorophenyl-phenylether	1,4-Dichlorobenzene

Acid Target Compounds

Benzoic Acid	2,4,6-Trichlorophenol
Phenol	2,4,5-Trichlorophenol
2-Chlorophenol	4-Chloro-3-methylphenol
2-Nitrophenol	2,4-Dinitrophenol
2-Methylphenol	2-Methyl-4,6-dinitrophenol
2,4-Dimethylphenol	Pentachlorophenol
4-Methylphenol	4-Nitrophenol
2,4-Dichlorophenol	

Pesticide/PCB Target Compounds

alpha-BHC	Endrin Ketone
beta-BHC	Endosulfan Sulfate
delta-BHC	Methoxychlor
gamma-BHC (Lindane)	alpha-Chlordane
Heptachlor	gamma-Chlordane
Aldrin	Toxaphene
Heptachlor epoxide	Aroclor-1016
Endosulfan I	Aroclor-1221
4,4'-DDE	Aroclor-1232
Dieldrin	Aroclor-1242
Endrin	Aroclor-1248
4,4'-DDD	Aroclor-1254
Endosulfan II	Aroclor-1260
4,4'-DDT	

Inorganic Target Compounds

Aluminum	Manganese
Antimony	Mercury
Arsenic	Nickel
Barium	Potassium
Beryllium	Selenium
Cadmium	Silver
Calcium	Sodium
Chromium	Thallium
Cobalt	Vanadium
Copper	Zinc
Iron	Cyanide
Lead	Sulfide
Magnesium	

DATA QUALIFIERS

QUALIFIER	DEFINITION ORGANICS	DEFINITION INORGANICS
U	Compound was tested for but not detected. The sample quantitation limit must be corrected for dilution and for percent moisture. For soil samples subjected to GPC clean-up procedures, the CRQL is also multiplied by two, to account for the fact that only half of the extract is recovered.	Analyte was analyzed for but not detected.
J	Estimated value. Used when estimating a concentration for tentatively identified compounds (TICS) where a 1:1 response is assumed or when the mass spectral data indicate the presence of a compound that meets the identification criteria and the result is less than the sample quantitation limit but greater than zero. Used in data validation when the quality control data indicate that a value may not be accurate.	Estimated value. Used in data validation when the quality control data indicate that a value may not be accurate.
C	This flag applies to pesticide results where the identification is confirmed by GC/MS.	Method qualifier indicates analysis by the Manual Spectrophotometric method.
B	Analyte was found in the associated blank as well as in the sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action.	The reported value is less than the CRDL but greater than the instrument detection limit (IDL).
D	Identifies all compounds identified in an analysis at a secondary dilution factor. If a sample or extract is re-analyzed at a higher dilution factor as in the "E" flag, the "DL" suffix is appended to the sample number on the Form I for the diluted sample, and <u>all</u> concentration values are flagged with the "D" flag.	Not used.
E	Identifies compounds whose concentrations exceed the calibration range for that specific analysis. All extracts containing compounds exceeding the calibration range must be diluted and analyzed again. If the dilution of the extract causes any compounds identified in the first analysis to be below the calibration range in the second analysis, then the results of both analyses must be reported on separate Forms I. The Form I for the diluted sample must have the "DL" suffix appended to the sample number.	The reported value is estimated because of the presence of interference.
A	This flag indicates that a TIC is a suspected aldol concentration product formed by the reaction of the solvents used to process the sample in the laboratory.	Method qualifier indicates analysis by Flame Atomic Absorption (AA).
M	Not used.	Duplicate injection (a QC parameter not met).

N	Not used	Spiked sample (a QC parameter not met).
S	Not used.	The reported value was determined by the Method of Standard Additions (MSA).
W	Not used.	Post digestion spike for Furnace AA analysis (a QC parameter) is out of control limits of 85% to 115% recovery, while sample absorbance is less than 50% of spike absorbance.
*	Not used.	Duplicate analysis (a QC parameter not within control limits).
+	Not used.	Correlation coefficient for MSA (a QC parameter) is less than 0.995.
P	Not used.	Method qualifier indicates analysis by ICP (Inductively Coupled Plasma) Spectroscopy.
CV	Not used.	Method qualifier indicates analysis by Cold Vapor AA.
AV	Not used.	Method qualifier indicates analysis by Automated Cold Vapor AA.
AS	Not used.	Method qualifier indicates analysis by Semi-Automated Cold Spectrophotometry.
T	Not used	Method qualifier indicates Titrimetric analysis.
NR	The analyte was not required to be analyzed.	The analyte was not required to be analyzed.
R	Rejected data. The QC parameters indicate that the data is not usable for any purpose.	Rejected data. The QC parameters indicate that the data is not usable for any purpose.

APPENDIX D


IEPA SITE PHOTOGRAPHS

EAGLE ZINC COMPANY



**Photo Location Map
Eagle Zinc Company**

- Legend**
- Soil
 - Sediment
 - Waste
 - Site Boundary



0 0.05 0.1 0.2 0.3 0.4
Miles

Source: Illinois Department of Natural Resources
Geospatial Data Clearinghouse:
Digital Orthographic Quadrangles, 1999, accessed 2005

Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE IL# : 980606941	COUNTY: Montgomery
TIME: 15:20	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: South.
Photo Number 1.
Sample X301 was collected at the southeast area of the site from a black cinder pile.




DATE: 4/25/05
TIME: 15:20
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 2.
Sample X301. The sample consisted of a fine black material collected at a depth of 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 15:40	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: North.
Photo Number 3.
Sample X302 was collected at the south area of the site from fine black cinders.



DATE: 4/25/05
TIME: 15:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 4.
Sample X302. The area contains little vegetation. Collected at a depth of 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 16:00	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: West.		
Photo Number 5.		
Sample X303 was collected at the southwest area of the site from a slag material.		



DATE: 4/25/05
TIME: 16:00
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: South.
Photo Number 6.
Sample X303. The sample consisted of a fine brownish gray material collected at a depth 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 16:10	SITE NAME: Eagle Zinc Co.	


PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: East.
Photo Number 7.
Sample X304 was collected at the southwest area of the site from a slag pile.



DATE: 4/25/05
TIME: 16:10
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: West.
Photo Number 8.
Sample X304. The sample consisted of an orange brown slag collected at a depth of 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 16:30	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: West.		
Photo Number 9.		
Sample X305 was		
collected at the		
southwest area of the site from a slag pile.		

DATE: 4/25/05
TIME: 16:30
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: South.
Photo Number 10.
Sample X305. The sample consisted of a fine black- brown slag collect- ed at a depth of 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 17:20	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 11.		
Sample X306 was collected at the southwest area of the site from a slag & cinder pile.		



DATE: 4/25/05
TIME: 17:20
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: West.
Photo Number 12.
Sample X306. The sample consisted of a gray material collected at a depth of 0 to ½ inches.



Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 17:40	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: East.
Photo Number 13.
Sample X307 was collected at the west central area of the site from a cinder/brick pile.



DATE: 4/25/05
TIME: 17:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: South.
Photo Number 14.
Sample X307. The sample consisted of a fine brown/ gray material col- lected at a depth 0 to ½ inches.



Expanded Site Inspection Addendum Photos

DATE: 4/25/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 18:15	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: east.
Photo Number 15.
Sample X308 was collected at the central area of the site from a slag pile.



DATE: 4/25/05
TIME: 18:15
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: West.
Photo Number 16.
Sample X308. The sample consisted of light gray slag fines collected at a depth of 0 to ½ inches.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 8:10	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 17.		
Sample X309 was collected at the northwest area of the site from a slag pile.		



DATE: 4/26/05
TIME: 8:10
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 18.
Sample X309. The sample consisted of a fine medium gray material with metal shavings, depth 0 to 1/2 inches



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 8:30	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: West.
Photo Number 19.
Sample X311 was collected at the west area of the site. Houses lie across the street.



DATE: 4/26/05
TIME: 8:30
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 20.
Sample X311. The sample consisted of a medium gray slag fines, from a depth of 0 to 1/2 inches.




Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 8:45	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: West.
Photo Number 21.
duplicate samples
X310/X312 collected
at the northwest
area of the site.



DATE: 4/26/05
TIME: 8:45
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 22.
Samples X310/X312.
Sample consisted
of a fine medium
gray slag material.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 9:30	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN
BY: R. Casper

COMMENTS: Picture
taken toward:
South.

Photo Number 23.

Sample X313 was
collected at the
northeast area of
the site from a
slag pile.



DATE: 4/26/05

TIME: 9:30

PHOTOGRAPH TAKEN
BY: R. CASPER

COMMENTS: Picture
taken toward:
North.

Photo Number 24.

Sample X313. The
sample consisted
of a fine light
gray material with
white fragments.

Depth 0 to ½ inches



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 10:30	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 25.		
Sample X210 was collected from a brownish-gray silty clay sediment at a depth of 3" to 5".		



DATE: 4/26/05
TIME: 10:30
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 26.
Sample X210 was consisted near the point where drainage from the site enters Lake Hillsboro.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 12:50	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN
BY: R. Casper

COMMENTS: Picture
taken toward:
West.

Photo Number 27.

Residential sample

X113 was collected

northwest of the

site from black

cinders and soil.



DATE: 4/26/05

TIME: 12:50

PHOTOGRAPH TAKEN
BY: R. CASPER

COMMENTS: Picture
taken toward:
East.

Photo Number 28.

Sample X113. The

sample was

collected at a

depth of 1 to 3

inches.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 13:40	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: South.
Photo Number 29.
Sample X209 was collected south of Smith road, in the offsite drainage pathway.



DATE: 4/26/05
TIME: 13:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 30.
Sample X209. The sample consisted of a brown sandy clay with some silt and organic material.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE IL# : 980606941	COUNTY: Montgomery
TIME: 14:30	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: South.
Photo Number 31.
Sample X208 was collected in the offsite drainage pathway south of Smith Road.



DATE: 4/26/05
TIME: 14:30
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 32.
Sample X208. The sample consisted of a brown silt. Collected at a depth of 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 15:00	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: West.
Photo Number 33.
Sample X207 was collected from the drainage pathway southeast of the site.



DATE: 4/26/05
TIME: 15:00
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: South.
Photo Number 34.
Sample X207. The sample consisted of a brown silt with a little sand and clay.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 17:00	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 35.		
Sample X206 was collected offsite east of Industrial Park Road.		



DATE: 4/26/05
TIME: 17:00
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 36.
Sample X206. The sample consisted of a brown silty clay, collected at a depth of 3 to 5 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/26/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 17:40	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: South.
Photo Number 37.
Sample X205 was collected onsite approximately 75 feet west of Indus- trial Park Road.



DATE: 4/26/05
TIME: 17:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 38.
Sample X205. The sample consisted of a brown silty clay collected from 0 to ½ inches.



Expanded Site Inspection Addendum Photos


DATE: 4/26/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 18:40	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: West.		
Photo Number 39.		
Duplicate samples		
X203/X204 collected		
onsite west of		
Industrial Park		
Road.		



DATE: 4/27/05
TIME: 18:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 40.
Samples X203/X204.
The samples
consisted of a
brown silty clay.
Collected 0 to 2
inches deep.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 8:50	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 41.		
Sample X202 was collected in the onsite drainage pathway.		

DATE: 4/27/05
TIME: 8:50
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: West.
Photo Number 42.
Sample X202. The sample consisted of a gray silty clay collected at a depth of 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 9:30	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 43.		
Sample X111 was collected from a residential yard west of the site.		



DATE: 4/27/05
TIME: 9:30
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 44.
Sample X111. The sample consisted of a black silty loam collected at a depth of 0 to 1 inch.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 9:50	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 45.		
Sample X112 was		
collected from a		
residential area		
west of the site.		



DATE: 4/27/05
TIME: 9:50
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 46.
Sample X112. The
sample consisted
of reddish-brown
cinders and slag,
collected from a
depth of 0 to 2".




Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 10:10	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 47.		
Sample X110 was collected from a residential area west of the site.		




DATE: 4/27/05
TIME: 10:10
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: West.
Photo Number 48.
Sample X110. The sample consisted of gravel, black fill material, cinders and metal pieces.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 10:50	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 49.		
Sample X107 was collected from a field west of the site near a residential area.		



DATE: 4/27/05
TIME: 10:50
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 50.
Sample X107. The sample consisted of a slag material over clay, collected at depth of 0 to 1 inch.



Expanded Site Inspection Addendum Photos


DATE: 4/27/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 11:40	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 51.		
Sample X104 was collected from a residential yard northwest of the site.		



DATE: 4/27/05
TIME: 11:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 52.
Sample X104. The sample consisted of a brown-black clay, collected at a depth of 0 to 1 inch.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 12:00	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: North.		
Photo Number 53.		
Sample X106 was		
collected from a		
public housing project northwest of the site.		

DATE: 4/27/05
TIME: 12:00
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 54.
Sample X106. The
sample consisted
of a brown-black
clay loam collected
at a depth of 0
to 2 inches.




Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 12:30	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 55.		
Sample X108 was		
collected from a		
residential yard		
west of the site.		



DATE: 4/27/05
TIME: 12:30
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 56.
Sample X108. The
sample consisted
of a light brown
clay loam collected
at a depth of 0
2 inches.




Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 12:50	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: West.		
Photo Number 57.		
Sample X114 was collected from a residential yard northwest of the site.		



DATE: 4/27/05
TIME: 12:50
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 58.
Sample X114. The sample consisted of a light brown clay loam collected a depth of 0 to 3 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 14:10	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: North.		
Photo Number 59.		
Samples X115/X105 collected from an athletic field complex north of site.		



DATE: 4/27/05
TIME: 14:10
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 60.
Samples X115/X105.
Duplicate samples consisting of cinders, slag material and black fines.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 14:50	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 61.		
Sample X116 was collected from a residential yard northeast of the site.		



DATE:
TIME:
PHOTOGRAPH TAKEN BY:
COMMENTS: Picture taken toward:
Photo Number

PHOTO NOT TAKEN

Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 15:20	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 62.		
Sample X201 was collected from lake Hillsboro at a residence located northeast of site.		



DATE: 4/27/05
TIME: 15:20
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: South.
Photo Number 63.
Sample X201. The sample consisted of a brownish gray silty clay collected at a depth of 2 to 4 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 15:50	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 64.		
Sample X118 was collected from a residential yard northeast of the site.		



DATE: 4/27/05
TIME: 15:50
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: West.
Photo Number 65.
Sample X118. The sample consisted of a dark brown silty loam collected at a depth of 1 to 3 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 17:20	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: North.		
Photo Number 66.		
Sample X109 was collected from a residential yard east of the site.		




DATE: 4/27/05
TIME: 17:20
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 67.
Sample X109. The sample consisted of a brown silty clay collected at a depth of 0 to 2 inches.




Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 17:40	SITE NAME: Eagle Zinc Co.	


PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: North.
Photo Number 68.
Sample X125 was collected from a residential yard southeast of the site.



DATE: 4/27/05
TIME: 17:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: South.
Photo Number 69.
Sample X125. The sample consisted of a black loam with gravel collected at depth of 0 to 3 inches.



Expanded Site Inspection Addendum Photos


DATE: 4/27/05	SITE ILD#: 980606941	COUNTY: Montgomery
TIME: 18:00	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: North.		
Photo Number 70.		
Sample X124 was collected from a residential yard southeast of the site.		

DATE: 4/27/05
TIME: 18:00
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 71.
Sample X124. The sample consisted of a fine black slag material.
Collected at depth of 3 to 6 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 18:50	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 72.		
Sample X123 was collected from a residential yard southeast of the site.		



DATE: 4/27/05
TIME: 18:50
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 73.
Sample X123. The sample consisted of a black silty loam with cinders collected at depth of 0 to 3 inch.



Expanded Site Inspection Addendum Photos

DATE: 4/27/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 19:20	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 74.		
Sample X122 was		
collected from a		
residential yard		
east of the site.		



DATE: 4/27/05
TIME: 19:20
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 75.
Sample X122. The
sample consisted
of a brown silty
loam collected at
a depth of 2 to 3
inches.



Expanded Site Inspection Addendum Photos

DATE: 4/28/05	SITE IL# : 980606941	COUNTY: Montgomery
TIME: 8:40	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: East.		
Photo Number 76.		
Samples X120/X121		
were collected from		
a residential yard		
east of the site.		



DATE: 4/28/05
TIME: 8:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 77.
Duplicate samples
X120/X121 consisted
of a light brown
silty clay collect-
ed at a depth of
0 to 1 inch.



Expanded Site Inspection Addendum Photos

DATE: 4/28/05	SITE IL# #: 980606941	COUNTY: Montgomery
TIME: 9:00	SITE NAME: Eagle Zinc Co.	

PHOTOGRAPH TAKEN BY: R. Casper
COMMENTS: Picture taken toward: East.
Photo Number 78.
Sample X126 was collected from a residential yard southeast of the site.



DATE: 4/28/05
TIME: 9:00
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: North.
Photo Number 79.
Sample X126. The sample consisted of a black silty loam collected at a depth of 0 to 2 inches.



Expanded Site Inspection Addendum Photos

DATE: 4/28/05	SITE ILID#: 980606941	COUNTY: Montgomery
TIME: 9:40	SITE NAME: Eagle Zinc Co.	
PHOTOGRAPH TAKEN BY: R. Casper		
COMMENTS: Picture taken toward: South.		
Photo Number 80.		
Sample X119 was collected from a facility located southeast of the site.		



DATE: 4/28/05
TIME: 9:40
PHOTOGRAPH TAKEN BY: R. CASPER
COMMENTS: Picture taken toward: East.
Photo Number 81.
Sample X119. The sample consisted of a black silty loam collected at a depth of 0 to 2 inches.

